

LARGE SCALE STRENGTH TESTING OF HEXCRETE SEGMENT DESIGN FOR TALL WIND TOWERS

Robert Pegg, PhD Candidate, Iowa State University, Ames IA
Sri Sritharan, PhD, Wilkinson Chair in the College of Engineering, Iowa State University, Ames, IA

ABSTRACT

To overcome the transportation and logistical challenges of using traditional steel tower designs with hub heights of 100 m (328 ft) and higher, Iowa State University (ISU) has developed a precast concrete wind tower known as the Hexcrete Tower. This tower technology has been further advanced with sponsorship from the U.S. Department of Energy (DOE) and a proof test of a full-scale Hexcrete tower unit was designed and fabricated to validate the tower design. The Hexcrete tower is a hexagon shape, precast concrete concept developed for tall towers using both High Strength Concrete (HSC) and Ultra-High Performance Concrete (UHPC). A 120-m tall Hexcrete tower was designed for a Siemens 2.3 MW turbine and a full-size section of the tower was assembled and tested at the Multi-Axial Subassemblage Testing (MAST) Laboratory in Minneapolis, Minnesota. The test unit successfully withstood both operational and extreme loads as a single system despite being formulated from a number of prefabricated elements. The overall performance of the tower met the necessary strength requirements, offered opportunities for improved design, and proved the Hexcrete concept as a competitive alternative to traditional steel for hub heights at or above 100 m.

Keywords: Energy, Hexagonal, Hexcrete, Tower, Turbine, Wind, Precast, Prestressed

INTRODUCTION

The Department of Energy (DOE) released the Wind Vision Report in 2015, which outlines the current state of wind energy in the United States (U.S.). The report explores new opportunities and directions for growth of the national wind energy market; summarizes the economic, social, and environmental impacts of increased wind production; and identifies future goals and technology advances that could directly impact future wind development¹. One of the future goals of the Wind Vision Report is for 35% of U.S. electric power to be generated by wind power by 2050¹. To accomplish this goal, technological advancement is needed and one such advancement is taller wind towers. For the purposes of this paper, tall towers will be defined as towers with hub heights above 100 m (328 ft).

Tall wind towers provide many benefits for energy production when compared to current tower technology. Wind speeds increase with height and are also less affected by natural or manmade terrain. The result is faster, steadier wind at higher elevations. Higher wind speeds are related to power production by a cubic relationship, which allows a significant increase in power production from a moderate increase in height. Larger towers also facilitate the opportunity to utilize longer blades which further increase production rates. In addition, some areas of the U.S., which do not utilize wind power due to minimal low level wind resources, would be able to generate wind power at higher heights². Therefore a cost-effective tall tower solution dramatically increases the opportunity to increase the U.S. energy production in order to meet the 35% milestone suggested by the DOE.

The current wind tower market is dominated by the 80 m (260 ft) steel shell tower. However, at higher hub heights, steel shells face limitations. The 80 m steel tower base is typically around 13-14 ft in diameter, but a 100-m tall tower would require the base to grow to around 18 ft in diameter³. The larger base prohibits cost-effective transportation due to the height of highway overpasses and lane widths. Steel shells can increase in thickness instead of growing in diameter, but this would result in almost doubling the volume of steel even for 100 m tall towers, significantly increasing material costs⁴. For these reasons precast concrete shell towers have begun to be implemented in Europe and South America⁵. Concrete shells are cast in smaller segments than circular steel tower sections, typically combining three to four shells which are joined together to make a full circular cross-section. The precast shells may require larger upfront cost due to the specialized formwork, but offer improved transportation options while using readily available concrete materials. Due to the use of reduced strength of concrete compared to steel, concrete towers often require large amounts of material, increasing the tower weight.

In order to fully realize the benefits of concrete towers, the Hexcrete concrete technology^{5,6} was developed by Iowa State University. The Hexcrete tower is a hexagonal shape concrete tower that utilizes high strength concrete materials and precast concrete shapes that do not require curved sections. Additionally, the tower consists of six hexagonal shaped columns and six flat wall panels that serve to connect the columns as shown in Figure 1. The columns and panels are linked by unbonded radial post-tensioning while unbonded vertical post-tensioning runs through the columns to secure the tower to the foundation as well as provide structural continuity. The tower is made out of a combination of Ultra-High Performance Concrete (UHPC) with a compressive strength of 26 ksi and High Strength Concrete (HSC) with a compressive strength of 13 ksi. Multiple Hexcrete towers were designed for hub heights at both 120 m and 140 m with sponsorship from the DOE, Iowa Department of Energy, and LaFarge North America. Industry partnerships for the project

included Siemens, BergerABAM, Coreslab Structures of Omaha, and the National Renewable Energy Labs (NREL).




Figure 1: Hexcrete wind tower concept

To validate the Hexcrete design methodology and further evaluate tower performance, a proof test of a full scale tower segment was designed and tested at the Multi-Axial Subassembly Testing (MAST) Laboratory in Minneapolis, Minnesota. In the following sections, the design and fabrication of the test unit is described as well as instrumentation and loading details. The goal of the test was to evaluate the strength of a critical Hexcrete tower segment under both operational and extreme loads. For design of wind towers, fatigue loads resulting from the dynamic response of the tower can also govern aspects of design. Therefore a separate fatigue test was conducted at Iowa State University with results that will be published in a subsequent paper. The MAST test provided an opportunity to evaluate the tower performance in regard to strength and stiffness, connection integrity, member cracking, and overall tower behavior when subject to combined moment, shear, axial, and torsional loads.

TEST UNIT DESIGN

The test unit was designed as a full-scale section of a 120-m tower housing a 2.3 MW-108 Siemens turbine. The test unit was designed to be identical in geometry to a section of the tower located at a height of 345 ft. This part of the tower was chosen based on the magnitude of the tower loads and the loading capacity of the MAST laboratory. The test unit section was 16.5 ft tall and 8 ft in diameter at the centerline of the tower section. The height of 16.5 ft was selected based on crane weight limitations within the laboratory. The overall dimensions of the test unit are shown in Figure 2. The test unit utilized both HSC and UHPC in order to validate the performance of each material in the Hexcrete tower system. Three columns and three panels were designed to be HSC and the other three columns and panels were UHPC. Using HSC and UHPC also offered the opportunity to directly compare the performance of each material throughout each stage of testing.




Figure 2: Test unit dimensions

To increase structural capacity and provide economical connections between members, the Hexcrete tower consists of both radial and vertical unbonded post-tensioning. The radial post-tensioning of the tower was not designed to be installed around the entire tower circumference. Instead, the radial tendons were divided into two overlapping groups in order to reduce the number of curves in each tendon as shown in Figure 3. The radial post-tensioning in the test unit consisted of 14 groups of four 0.6 in. 270 ksi relaxed tendons which translated to seven circumferential groups of tendons along the test unit height with an average spacing of 2.25 ft (Figure 3). The radial post-tensioning in the test unit consisted of 14 groups of four 0.6 in. 270 ksi relaxed tendons which translated to seven circumferential groups of tendons along the test unit height with an average spacing of 2.25 ft (Figure 3). The 120-m Hexcrete tower was designed with one set of vertical post-tensioning tendons per column, which extend the entire height of the tower. The critical design section for determining the number of tendons in a single column is typically located at the base of the tower which results in reserve capacity at higher tower elevations. Since the test unit section was located at a height of 345 ft, the number of vertical tendons in the test unit was reduced from the original tower design in accordance with the capacity demands at the base of test unit. This resulted in a group of twenty tendons in each column of the test unit.




Figure 3: Radial tendon layout (left); radial and vertical tendon locations along test unit height (right)

Foundation blocks and top reaction blocks were designed to anchor the vertical post-tensioning and also to attach the tower test section to the strong floor and loading crosshead, respectively. The depth of the blocks was determined by the space necessary to ensure proper anchorage of each set of post-tensioning tendons. Load cells were fabricated to fit underneath the post-tensioning anchors in the top blocks, which resulted in additional top block depth. All post-tensioning anchorage locations for tendons in the Hexcrete tower and test unit were designed to follow code requirements for allowable stress limits from the American Concrete Institute (ACI), namely the concrete stress limit of $0.45f'_c$ specified for sustained load conditions. The tendons used in the test unit design were 270 ksi relaxed seven-wire tendons.

TEST UNIT CONSTRUCTION

The precast concrete pieces for the test unit were fabricated at Coreslab Structures in Omaha, Nebraska, as shown in Error: Reference source not found and then shipped to MAST (Error: Reference source not found). The test unit was constructed in two halves due to space and lifting limitations within the lab. Each half consisted of a single foundation block, three columns, two panels, and a single top block. This construction approach did not benefit the two panels that would connect the test unit halves, since the panels would not be subject to precompression from the vertical post-tensioning, but was necessary due to laboratory limitations. A temporary support frame was constructed to hold the columns and panels in place during the construction process as shown in Error: Reference source not found.





Prior to positioning the columns on the foundation, grout forms and steel shims were placed at the column locations for grouting the column-to-foundation interface. The columns were set in place on the steel shims and attached to the support frame. The grout pads were not poured at this time in order to allow adjustment of the columns during placement of the connecting wall panels. The wall panels were then positioned between the columns and attached to the support frame for stability. The tower segment was designed with a 0.75 in. gap between each column and panel to allow for construction tolerances. High strength epoxy was applied in this gap in order to provide a uniform bearing surface for radial post-tensioning. The epoxy was mixed and then manually packed into the joints between the columns and panels using trowels. No compression force was applied to the joint during the curing process. After curing of the epoxy, six 0.5 in. diameter tendons were utilized to temporarily connect the columns and panels. Two tendons were placed through the top, middle, and bottom of the half test unit and subsequently tensioned to an effective stress of 126 ksi per tendon. The half test unit was not yet permanently attached to the foundation block, but the self-weight of the pieces and the support frame kept the members in place during the temporary radial tensioning. Grout pads were then poured at the top of the columns, the top block was set in place, and the vertical post-tensioning tendons were installed. At this time, the grout pads at the base of the columns were also poured. After all the grout pads were sufficiently cured, the vertical post-tensioning was tensioned to an effective stress of 163 ksi per tendon and the support frame was removed. The half test unit was then lifted into its final position for testing and attached to the MAST strong floor. The second half of the test unit was constructed using the same method, moved into the correct position and attached to the strong floor as well.

After both halves of the test unit were attached to the strong floor, the temporary post-tensioning between the columns and panels was removed, the final two panels were placed, and epoxy was installed at the column interfaces for these two panels. After curing of the epoxy, radial 0.5 in. diameter post-tensioning tendons were run through the columns and panels to connect the entire unit and tensioned to an effective stress of 166 ksi per tendon.

The original tower design included 0.6 in. diameter tendons instead of the 0.5 inch. However, placement of the 0.6 in. tendons in the test unit was not possible due to the curvature of the post-tensioning ducts combined with the duct's corrugated inner surface. Although this challenge can be easily overcome in a prototype tower by using larger ducts, 0.6 in. tendons were substituted with 0.5 in. tendons in the test unit, and the panel stresses and joint interface forces were reexamined to understand how the smaller tendons would affect the test unit capacity. It was calculated that both the HSC and UHPC panels should not crack under operational or extreme torsional loads with the smaller tendons. However, the smaller tendons resulted in a weaker interface between the columns and panels due to lower precompression of the joint. After completion of the radial post-tensioning, the test unit was attached to the testing crosshead to allow load application.

INSTRUMENTATION

To adequately capture the test unit behavior, an extensive instrumentation scheme was used. Four types of instruments were used to collect test data: strain gages, string potentiometers (string pots), Linear Variable Displacement Transducers (LVDTs), and an Optotrack 3D camera system. Strain gages were placed on rebar at the precast plant near post-tensioning locations in order to monitor the effects of the vertical post-tensioning on the foundation and top blocks. Concrete strain gages were also placed on the surface of two concrete panels (one HSC and one UHPC) to monitor and compare stresses in the panels. String pots were attached to four of the test unit columns in order to record the overall test unit displacement. LVDTs were placed in order to measure displacement at the column to panel connections as well as between the columns and the foundation and top blocks. The Optotrack camera system measured panel stresses on a UHPC panel to compare with the concrete strain gage stress. An overview of the test unit instrumentation is shown in Figure 4.




Figure 4: Instrumentation of test unit

TEST UNIT LOADS

Once the instrumentation of the test unit was complete, a loading protocol was formulated in order to investigate the tower section behavior under operational and extreme loads. Three design load cases (DLCs) as defined by the International Electrotechnical Commission (IEC) 61400-1 were considered in order to accurately simulate the maximum operational and extreme forces experienced by the tower section. Each load case included a shear force, overturning moment, axial force, and torsional moment. The first load case was IEC DLC 1.1, where the resultant loads are caused by atmospheric turbulence under normal tower operation⁶. This load case generates the largest tower overturning moment for both operational and extreme load conditions. The second load case was IEC DLC 4.2, which corresponded to the wind turbine switching from power production to an idle or stand still position⁶. The change in position generates the largest tower shear force at operational and extreme loads. The last load case was IEC DLC 2.2, which corresponded to an electrical fault in the control protection system and results in the largest tower torsional moment at operational and extreme conditions⁶. For operational and extreme loads the test unit was displaced in four directions in both positive and negative orientations shown in Figure 5.




Figure 5: Test unit loading directions

TEST RESULTS

Following the construction and instrumentation of the test unit, the loading process was initiated. For both operational and extreme loads, two critical parameters were identified to evaluate the response of the tower test section. The first parameter was the stiffness of the tower section during loading, which was defined in terms of the load versus displacement response of the structure. The test unit was designed to remain elastic under both operational and extreme loads. The second critical response parameter was concrete cracking in the test unit members including both the crack location and crack size. Although the test unit was designed remain uncracked under operational and extreme loads, the reduction in horizontal post-tensioning could influence this response.

Operational loads were the first set of loads applied to the test unit. For each load case the loads were applied in 25% increments until the full load was reached. The operational loads corresponding to DLC 1.1 and 4.2 were applied with no observable damage and small amounts of deflection as shown in Figure 6 and Figure 7. For the torsional loading of DLC 2.2, the test unit responded in a linear manner (Figure 8); however, hairline cracks were observed on all the HSC panels at 100% load. The two HSC panels which connected the two test unit halves during construction experienced moderate amounts of cracking as shown in (Error: Reference source not found) while only a single crack appeared in the third HSC panel. These cracks, which were marked with a black marker for visibility, did not exceed a width of

0.004 in. No further damage was observed under operational loads. The cracks also completely closed upon unloading of the test unit.

Figure 6: DLC 1.1 – Operational overturning moment response

Figure 7: DLC 4.2 – Operational shear response

Figure 8: DLC 2.2 – Operational torsional response



As previously stated, the HSC panels were not designed to crack under operational torsional loads. After further investigation of the data collected from the panel instrumentation, it was determined that the construction sequence and use of smaller radial tendons were both responsible for the observed cracking. The vertical post-tensioning introduced a larger amount of precompression in the panels than was predicted before the test and this precompression was not present in the connecting panels. The reduction in radial post-tensioning also contributed to the panel cracking in contrast to the calculations performed at the time of construction.

After completion of the operational loads, extreme load values were applied to the test unit. No damage occurred in the test unit when loads for DLC 4.2 and DLC 1.1 were applied and the test unit continued to behave in an elastic fashion as shown in and Figure 10. At 75% application of the extreme torsional load (DLC 2.2), new 0.004 in. cracks were observed on the base of one of the two HSC connecting panels as shown in Error: Reference source not found. The original cracks that occurred during operational loading, increased in width to 0.008 inches. Additional 0.004 in. cracks also appeared on the connecting HSC panels at 100% extreme torsional load, a single new crack appeared at the base of the third HSC panel, and 0.004 in. cracks formed on one of the UHPC columns. The cracks on the UHPC column were localized around a radial PT anchorage location as shown in Error: Reference source not found, which appears to lack steel fibers in the UHPC at this location. These type of cracks did not appear in any other columns which reinforces the idea that the problem is a local issue. UHPC fiber distribution can be improved by reducing the amount of reinforcement in the columns and based on the observed performance of the test unit, it is expected that the column reinforcement can be reduced. It is also important to note that the panel cracking was limited to HSC panels and that UHPC panels did not experience cracking under torsional loads. The absence of cracks in the UHPC panels is due to the higher tensile capacity of UHPC. After applying 100% of the extreme torsional load DLC 2.2, the force-displacement response of the test unit continued to be linear with no decrease in strength as shown in Figure 11. As was the case for operational loads, all cracks closed completely when the loads were removed from the test unit and no further damage to the test unit was observed.

Figure 9: DLC 4.2 - Extreme overturning moment response

Figure 10: DLC 1.1 - Extreme shear response



Figure 11: DLC 2.2: Extreme torsional response

Since the test unit force-displacement response remained linear after the application of extreme loads, large magnitude loads were applied in order to measure the full capacity of the unit and also identify the failure mechanism of the tower system. To reach the test unit capacity, loads corresponding to the operational and extreme design envelopes were applied to the test unit. The design envelopes were a combination of all three load cases originally applied to the test unit. A small number of 0.004 in. cracks were observed on the HSC connecting panels under the operational load envelope, but no further damage or change in stiffness was observed during the lateral (Figure 12) and torsional (Figure 13) test unit responses. However, at the extreme load envelope, a drop in torsional stiffness was observed as shown in Figure 14. The change in stiffness was due to further cracking of the connecting HSC panels and separation in the epoxy joints between multiple UHPC panels and the test unit columns.

Figure 12: Operational envelope lateral response

Figure 13: Extreme envelope torsional load

Figure 14: Extreme envelope torsional response

The test unit retained a large amount of load capacity after the decrease in stiffness, and therefore, torsional displacements were continuously applied in increasing magnitude beyond the extreme load envelope. Damage to the test unit progressed steadily as the torsional displacement increased beyond 1 degree of rotation (1 degree of rotation was five times the rotational displacement for extreme torsional loading). Both HSC and UHPC columns experienced torsional cracking, new cracks continued to appear on the HSC panels, and the epoxy between all of the column and panel connections began to crack or split vertically. The UHPC panels did not experience visible cracking, but gaps up to 0.25 in. opened between the UHPC panels and columns at the epoxy joint. At 4 degrees of rotation spalling had occurred on both HSC and UHPC columns and the test was terminated due to damage to the foundation blocks which made continuation of testing potentially unsafe. The progression of damage to the test unit during the large displacement cycles is shown in Error: Reference source not found while Figure 15 shows the tower rotational displacement response. Much of the damage to the test unit was spalling of cover concrete which protects the steel reinforcement from corrosion. The cover concrete does not significantly affect the structural capacity of the test unit and the unit was still able to support the axial load simulating the weight of the nacelle and rotor after the completion of testing. The response of the test unit



under large



displacements demonstrated that the tower had sufficient ductility beyond extreme loads.

Figure 15: Large rotational displacement response

CONCLUSION

The primary objective of the Hexcrete unit test was to validate strength capacity of the tower design process and demonstrate that the assembled precast pieces can act as a single unit to resist both operational and extreme loads in an elastic manner. Based on the operational and extreme load performance of the test unit, it can be concluded that the test unit did act as a single unit and remained elastic through both operational and extreme loads. Premature cracking of the test unit was observed on the connecting panels as the result of the test unit construction sequence and use of smaller radial tendons. Both issues will be eliminated in prototype construction of the tower system since the entire Hexcrete cross-section is built and stacked before vertical post-tensioning is applied and larger ducts can be utilized for the radial tendons. The UHPC panels in the test unit did not experience any cracking through the operational and extreme loading cycles. Localized cracking also occurred at one UHPC column anchorage location and was due to a lack of steel fiber distribution in the UHPC. This cracking can be prevented with proper casting procedures. In summary, despite premature cracking, no loss in strength or change in tower stiffness occurred in either the lateral or torsional tower response for both operational and extreme loads. The tower section continued to carry axial load and maintained structural integrity even after the application of large torsional displacement cycles. The test results validate the strength capacity of the Hexcrete tower system and identify UHPC as the preferable material for the Hexcrete tower panels. When these results are combined with proven fatigue performance, the Hexcrete tower technology is a suitable precast concrete design for building tall towers to reach the DOE Wind Vision goal for 2050.

REFERENCES

1. Department of Energy. (2015). *Wind Vision: A New Era for Wind Power in the United States*.
2. National Renewable Energy Lab. (2016, June). *NREL Wind Resources*. Retrieved from <http://www.nrel.gov/wind/news/2015/19541.html>
3. Lewin, Thomas James, "An investigation of design alternatives for 328-ft (100-m) tall wind turbine towers" (2010). *Graduate Theses and Dissertations*. Paper 12256.
4. Acciona Wind Power. (2016, June). *Concrete Towers*. Retrieved from <http://www.acciona-windpower.com/technology/concrete-towers/>
5. Sritharan, S., T. Lewin, and G. M. Schmitz. 2014. Wind turbine tower systems. U.S. Patent 8,881,485, filed May 13, 2014, and issued November 11, 2014.
6. Sritharan, S. and T. Lewin. 2015. Wind turbine tower systems. U.S. Patent 9,016,012, filed May 23, 2012, and issued April 18, 2015.

ACKNOWLEDGEMENTS

The information, data, or work presented herein was funded in part by the Office of Energy Efficiency and Renewable Energy, U.S. Department of Energy, under award number DE-EE0006737 (<http://sri.cce.iastate.edu/hexcrete/>). Additional funding and in-kind support have also been obtained from Iowa Energy Center and Lafarge North America Inc. of Chicago, Ill., respectively.

Members of the project team include Sri Sritharan, Ming-Chen Hsu, David Jeong, Julienne Krennrich, Shubin Lin, Hart Wibowo, Robert Peggar, Bin Cai, Phil Barutha, Ali Nahvi, and Cheng-Hao Wu of Iowa State University; Suraj Musuvathy and Sanjeev Srivastava of Siemens Corp.'s Corporate Technology; Todd Culp of Coreslab Omaha; Markus Wernli and Miranda Hagadorn of BergerABAM Inc.; and Jason Cotrell and Tyler Stehly of the National Renewable Energy Laboratory.

The author also thanks industry representatives who participated in the workshop that focused on the Hexcrete tower production and erection and provided further input for estimating construction and erection costs for the 120 m (394 ft) tall Hexcrete tower. The participants included Kevin Dieter of Pattern Energy, Jon Grafton of Oldcastle, David Dieters of Midstate Precast, Ken Fleck of Patterson, Daniel Harger of Structural Technologies VSL, Mark Strzok of Bigge Crane and Rigging, and Kirk Morgan of Barr Engineering. Additional input for this effort was also obtained from Dan Juntunen and Tim Edland of Wells Concrete in Minnesota.

DISCLAIMER

The information, data, or work presented herein was funded in part by an agency of the U.S. government. Neither the U.S. government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the U.S. government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the U.S. government or any agency thereof.